



NEW NICE/MIDDLETON BRIDGE Replacement Project

Contract Number: NB-0543-0000 Governor Harry W. Nice/Senator Thomas "Mac" Middleton Bridge Replacement Design-Build Project

AISC Steel Days / High Steel Open House 10-19-2023



SKANSKA SCORMAN McLean

AECOM







With General Engineering Consultant (GEC) JV







Construction Inspection Team

















Design-Build Contractor

SKANSKA ZCORMAN MCLean

In partnership with

AECOM





Designers



























Independent Design Quality Manager - IDQM









Nice Bridge Fast Facts

- Construction dates: March 1938 December 1940
- Original cost to construct: \$5 million
 - ✓ New Bridge cost \$462,957,000
- Named in 1968 for Maryland Governor Harry W. Nice
 - ✓ Renamed in 2018 to include Senator Thomas "Mac" Middleton
- Length of entire facility (including bridge and approaches): 2.2 miles
- Bridge length: 1.9 miles of two-lane bridge
- CY 2019 traffic volume: 6.6 million vehicles (average annual daily traffic: 18,200)
- FY 2019 toll revenue: \$21.0 million







Existing Bridge

- Designed by Greiner now AECOM
- Two-Lane Steel Bridge
- Steel Beam Approach Spans
- Rhomboid Girder Approach Spans
- Truss Approach Spans
- Through Cantilever Truss Main Span







Most Significant Needs for New Bridge

- Severe Summertime Traffic
 - \checkmark Routine weekend backups up to 4 miles
- Lane closure limitations for maintenance
 - ✓ Flagging operations required
- Safety Issues
 - ✓ Certain crash types more than double the Statewide averages







Process & Timeline

- June 2018 Multiple Pre-Solicitation Conferences
- October 20, 2018 RFQ Advertised
 - ✓ November 9, 2018 held Pre-Proposal Conference
 - \checkmark Short listed the four (4) most highly qualified teams
- March 8, 2019 RFP issued to reduced candidate list
- Procurement team processed:
 - ✓ 435 questions in 20 confidential one-on-one meetings (5 per team)
 - ✓ 96 Alternative Technical Concepts from the teams
 - ✓ 420 questions answered via 14 addendums
- July 30, 2019 Technical Proposals received
- September 6, 2019 Price Proposals received
- October 4, 2019 Notice of intent of award issued to Skanska-Corman-McLean (SCM) team
- October 23, 2019 SCM team approved to commence early submittals
- November 21, 2019 MDTA Board approval of SCM team
- January 24, 2020 SCM team awarded the Contract
- October 12, 2022 Bridge opened to traffic





Authority





The greatest economy in the design of any structure is attained by making the structure as simple as possible and with the greatest amount of duplication of spans, superstructure, substructure, and foundations. Everything becomes less time consuming and costly including shop drawings, fabrication, and erection. Repetition not only results in faster construction, but also results in higher quality.







- MDTA provided sufficient engineering data and comprehensive Performance Specifications, as well as other pertinent information to help make key decisions during the proposal phase design (Greatly reduced DB Teams Risk).
- Primary objectives during the design-build proposal phase was to evaluate the most economical, durable and constructible bridge types:
 - Understanding river mechanics & scour;
 - Foundation requirements;
 - Climate and exposure conditions as they relate to durability; and
 - Constructing the bridge in an aggressive marine environment.
- The level of development accomplished during the proposal phase facilitated starting construction as quickly as possible after project award (within 6-months).





- Foundations provide the greatest potential for cost savings:
 - Seven (7) foundation types and sizes were evaluated including concrete square piles, concrete cylinder piles and steel pipe piles. Pile lengths ranged from 69-feet to 191-feet in length with nominal bearing resistances between 1,200 to 3,115-kips
- Design Repetition increases production and improves quality (i.e. assembly line process) by maintaining families of bridge component sizes for columns, pier caps, footings, pile types & layout, etc.
- Water Line Footings results in direct savings by eliminating costly coffer cells
- Precast Foundations & Superstructure allows bridge component production to start early, compresses the schedule by accelerating erection, and improves overall quality because the concreting and curing are done in a controlled environment as opposed to in the air over water
- Span Optimization considering the number of spans & span lengths cost balanced against the number and heights of piers and supporting foundations





- Eight (8) superstructure types were evaluated for a wide range of span length arrangements including PSC girders, spliced PSC concrete girders, steel girders, and precast concrete segmental box girders
- The 9,966-feet long bridge (1.9-miles) is optimally divided into three distinct sections including the Low-Level Approach Spans, High-Level Approach Spans, and Main Channel Spans
- Design focused on consistent spans, constant depth, consistent colors, clean lines, gradual curvature's sight line, and openness to improve overall aesthetics











Span Configurations



- Low-Level Spans 79" Bulb-T's (150-ft typ span)
- High-Level Spans 95" Bulb-T's (175-ft typ span)
- Main Channel Spans Steel Plate Girders (285'-350'-285')









Design Criteria

AASHTO LRFD Bridge Design Specifications

MDOT Office of Structures Structural Details Manual

MDOT Office of Structures Guidelines, Policies and Procedures Memorandums

Performance specifications

75-year service life

Pier protection system





Alternative Technical Concepts

- Pile spacing reduction from 3D to 2.5D
- Concrete deck design per AASHTO LRFD
- Steel girder spacing increase from 10'-6" to 10'-10"

Governor Harry W. Nice / Senator Thomas "Mac" Middleton Bridge Replacement Design-Build Project

Key Elements in Final Bridge Design and Construction







Bridge Foundations

Prestressed Concrete Piles (7,000 psi):

- 36" square piles for High-Level & Low-Level Approach Spans
 - ✓ Solid
 - ✓ Plain Prestressing Steel Strands (32 @ 0.6")
 - ✓ 100-ft to 190-ft Long (combined water and soft soils range 70 to 150-ft)
 - ✓ NBR up to 1,566 kips
- 66" cylinder piles for Main Channel Spans
 - ✓ CFRP strands (36 @ 0.6")
 - ✓ Up to 188-ft Long
 - ✓ NBR up to 1,966 kips







Bridge Foundations

- Loads distributed based on effective stiffness
 - Pile foundation stiffness
 - Pier stiffness
 - Bearing stiffness
 - Scoured and unscoured condition
- FB-MultiPier
- High Level -16 to 28 piles
- Main Channel 20 piles





Maryland Transportation Authority

Bridge Foundations

Scour

- 100-yr storm for all load cases
- 500-yr storm for extreme event load case
- FB-MultiPier models considered both scoured and unscoured conditions.
- 3.5' to 16.5' for 100-yr
- 7.1' to 23.8' for 500-yr















- 6 or 7 piles
- FRP jackets in splash zone
- 200-ton barge impact (water depth > 2-ft)
- For climate change and sea level rise, the RFP required a bottom of superstructure elevation above the Maryland Coast Smart Council construction requirements = El 12.62 (500-year flood elevation at 6.82)









High-Level Approach Spans – Waterline Footings

- Precast tubs
- 7-ft deep
- 16 to 28 pile groups
- Piles embedded 3.5' with #11 dowels (galvanized)
- 200-ton barge impact







High-Level Approach Spans -Substructure

- Two Column Piers w/ diameters 6'-6" to 8'-6"
 - 6'-6" for pier heights up to 51-ft
 - 7'-6" for pier heights up to 86-ft
 - 8'-6" for pier heights up to 120-ft







Substructure

- High Level and Main Channel
- Typical pier cap 61' long, 8' deep,
 9' wide
- Cap widths provide room for bearing replacement

Pier Cap Reinforcement







Expansion Joint Pier Cap



- VDOT trough on pier cap
- RFP requirement
- Trough is precast in two sections







Main Channel Spans – Waterline Footings

- Precast tubs
- 9-ft deep
- 20 pile group
- Piles embedded 3.5' w/ #11 dowels
- Interior filled with sand up to concrete plug
- Vessel Pier Protection















Vessel Pier Protection

- 48" diam steel pipe piles
- A572 Grade 50
- $1\frac{1}{2}$ " wall typical
- $1 \frac{7}{8}$ wall in fixity zone
- Shear rings near pile head
- 8' of embedment into cap
- 22' filled with 8 ksi concrete
- FRP jacket





Vessel Pier Protection

- 5,000 DTW at 8 knots (42 annual vessels each direction)
- Reinforced concrete ring
 - Precast with CIP closures
 - Voided (foam filled) provided to reduce P-delta effects
 - Designed for large deformations
- Composite lumber
- Must maintain 250' horizontal channel clearance





NEW NICE MIDDLETON BRIDGE





Pier Supported Gantries





- Gantries required for lane use control signals
 - Spaced approximately 1,000-ft
- Electrical platforms at some piers
- Pier caps 69'-6" long





Main Channel Spans Superstructure



- 285' 350' 285'
- Variable depth plate girders (114" to 144")
 - HPS 70W flanges
 - Grade 50 webs
- 9" deck with low carbon/chromium steel
- 42" F-Shape Parapet
- Lateral bracing in exterior bays
- 1" diameter A325 bolts















Main Channel Spans Superstructure

- Evaluated against potential wind excitation when L/W>30 or as required by AASHTO. T < 1.0 second
- RWDI performed climatological analysis to establish critical wind conditions
- Provided project required wind speeds for wind loading and aerodynamic stability
- Desktop (computer modeling) assessment of aerodynamic stability
- Determined risk of vortex shedding induced vibrations (VIO) at 30 to 50 mph
- Sectional Model testing performed with various wind faring options
- Buffeting Analysis provided equivalent static wind loads

Table 2-1b: Recommended Wind Speeds at Bridge Site, AASHTO 8th Edition

Wind Speed Applicable for	Return Period (years) 28	Mean Wind Speed (mph) at Deck Level 150 ft and Averaging Time		Corresponding 3- second Gust Speed (mph) atC 33 ft Open Terrain
Design during construction		64	1 h	85
Design of completed bridge	1400	85	1 h	112
Stability during construction	1,000	79*	10 min	101*
Stability of completed bridge	10,000	90*	10 min	116*

*Includes reduction due to extreme wind climate directionality






Wind Evaluation & Testing

- Site Specific Wind Study
- Section Model Tests
- Vortex-Induced Oscillations
 - Onset Wind Speed < 50 mph

- Mitigation Strategies

- Tuned Mass Dampers (TMD)
- Wind Fairings
- ✓ 5% Increase Stiffness/Frequency (6" Increase Web Depth)

- Design Wind Loads

- ✓ RWDI Buffeting Loads
- ✓ AASHTO Wind Loads









Main Channel Spans Superstructure

- **Carboline Coating System**
- -33-year service life
- -3 Coat system
 - Primer: Carbozinc 11HS @ 3.0-5.0 mils DFT
 - Stripe Coat: Carbozinc 859 applied at all weld seam, corners, edges.
 - Intermediate Coat: Carboguard 893 @ 5.0-8.0 mils DFT
 - Finish: Carboxane 2000 @ 5.0-7.0 mils DFT





Main Channel Spans Superstructure

1570-Kip Disc Bearings









Modular Expansion Joints



24" movement range



SECTION B-B (JOINT TYPE 1) SCALE: 1/2" = 1'-0"

9" movement range







Field Operations









Logistics - Maryland





Logistics - Virginia





Heavy Lift and Marine Equipment

(2) 888 Ringers, (1) 4100 Ringer, (2) Whirley Cranes During peak period the project employed over 20 cranes, over 30 barges, and 5 tug boats



Equipment – Concrete Batch Plant/Barge Loading

McLean

SKANSKA SCORMAN





SKANSKA SCORN



Marine Concrete Delivery

McLean

(2) Transport Barges w/ (2) lines of (3) 15CY Agitors(1) Placing Barge with (2) Remixers, (1) Pump, (1) Placing Tower/Boom



Piling

- 36" Square Piles approx 740 piles Avg 166' (112 Ton) Long 206' (139 Ton)
- 66" Cylinder Piles 80 Piles Avg 187' (122 Ton) Long 200' (131 Ton)
- Test Piles (indicator/load test) used as production piles
- Piles delivered via barge from Cape Charles VA

SKANSKA SCOR

- Pile hammers included hydraulic, air, and diesel hammers
- Pile rigging employed a through pin lifting assembly in lieu of "choking" with slings



McLean

SKANSKA SCORMAN McLean

Pile Driving – "A" Frame Leads

Barges with "A" frames positioned using anchor lines and GPS







Pile Driving – Template





Pile Driving – Hanging Leads







Waterline Foundation – "Bathtub"







SKANSKA SCORN

Waterline Foundation – Precast "Bathtubs"

McLean

- Piles driven to elevation or cut to elevation using diamond wire saw
- Custom hanging system with embeds cast into bathtub
- Soffit forms, hung from piles prior to placing precast, are drawn up to the bottom of the foundation and grouted.
- Bathtub is pumped out, cleaned, and prepared for concrete fill with installation of pile dowels and reinforcing

SKANSKA SCORMAN McLean

Pier Protection System

(24) Precast sections (12 per pier X 2 piers) Range 185 Tons to 220+ Tons



















Prestressed Girder Erection



Low Level 27 Spans (79" PCEF) 6 Girders per span (qty 162) 3 Spans @ 125' 24 Spans @ 150'

High Level 29 Spans (95" PCEF) 7 Girders per span (qty 203) All @ 175'

Majority tandem picks Unit weight range 73T to 112T



Superstructure Team Members





Superstructure – Steel





Project Timeline – Steel Spans

JV Agreement formed Winter 2016 MDTA Notice of selection Fall 2019 MDTA Notice to Proceed March 2020 Main Channel Superstructure Released for Construction Dwgs. Nov.2020 Subcontract for Structural Steel December 2020 Shop Drawing Initial Submission February 2021



Initial Shop Visit April 2021 Start of Fabrication June 2021 Complete Fabrication and Coating October 2021 Start field activities October 2021 Complete field activities March 2022









 NAME AND ADDRESS OF TAXABLE PARTY OF TAXABLE PARTY.

Attacking COVID Together

Mitigating a 3-month gap between original schedule and forecasted completion

Changes to field activities – move erection start from Sept to Oct.

Reduce trial assemblies – cut 45 days from final ship date

2HIG An Attivute of H		EEL RUCTURE	IS uc				
	Esh Start	Esh complete	Vard start	Vard complete	Paint start	Paint complete	Ready to shi
span	rau start	7/15/2021	N/A	M/A	7/26/2021	7/30/2021	8/2/2021
8	-	7/23/2021	N/A	N/A	7/26/2021	8/6/2021	8/9/2021
6		112314944	7/75/2021	9/0/2021	8/10/2021	8/20/2021	8/23/2021
	-	8/20/2021	7/26/2021	8/9/2021	8/10/2021	9/24/2021	9/27/2021
F		8/13/2021	7/26/2021	8/9/2021	8/10/2021	8/20/2021	8/23/2021
F	7/26/2021	8/20/2021	N/A	N/A	8/23/2021	8/27/2021	8/30/2021
G	8/2/2021	8/27/2021	8/16/2021	8/27/2021	8/30/2021	9/8/2021	9/9/2021
.18	- X	10/4/2023	- 8/16/2021	8/27/2021	8/30/2021	10/22/2021	10/25/2021
- 1	x	8/2/2021	8/16/2021	8/27/2021	8/30/2021	9/8/2021	9/9/2021
1	×	9/3/2021	N/A	N/A	9/7/2021	9/13/2021	9/14/2021
		7/20/2021	41/4	11/4	0/20/2021	0/2/2022	

Harry Nice Bridge - Main Channel Steel Fabrication vs Required on Site Dates

L						
ke						
	Receive	Receive	High Stl	High Stl	Variance	Variance
rders	on Site	on Site	Date	Date		
Lines	Start	Finish	Start	Finish	Start	Finish
1 to 6	20-Sep	23-Sep	23-Aug	27-Sep	28	-4
3 to 6	30-Sep	7-Oct	9-Aug	23-Aug	52	45
1&2	14-Oct	18-Oct	2-Aug	9-Aug	73	70
1 to 6	25-Oct	27-Oct	9-Sep	25-Oct	46	2
3 to 6	4-Nov	11-Nov	16-Aug	9-Sep	80	63
1&2	18-Nov	22-Nov	16-Aug	23-Aug	94	91
3 to 6	26-Nov	3-Dec	30-Aug	9-Sep	88	85
1&2	10-Dec	14-Dec	23-Aug	6-Sep	109	99
	ders Lines 1 to 6 3 to 6 1 & 2 1 to 6 3 to 6 1 & 2 3 to 6 1 & 2 3 to 6 1 & 2	Receive ders on Site Lines Start 1 to 6 20-Sep 3 to 6 30-Sep 1 to 6 25-Oct 3 to 6 4-Nov 1 & 2 18-Nov 3 to 6 26-Nov 1 & 2 10-Dec	Receive Receive lines Start Finish 1 to 6 20-Sep 23-Sep 3 to 6 30-Sep 7-Oct 1 k 2 14-Oct 18-Oct 1 to 6 25-Oct 27-Oct 3 to 6 4-Nov 11-Nov 1 & 2 18-Nov 22-Nov 3 to 6 26-Nov 3-Dec 1 & 2 10-Dec 14-Dec	Receive Receive High Stl Image: Start Finish Start 1 to 6 20-Sep 23-Sep 23-Aug 3 to 6 30-Sep 7-Oct 9-Aug 1 to 6 25-Oct 27-Oct 9-Sep 1 to 6 25-Oct 27-Oct 9-Sep 3 to 6 4-Nov 11-Nov 16-Aug 1 & 2 18-Nov 22-Nov 16-Aug 3 to 6 26-Nov 3-Dec 30-Aug 1 & 2 10-Dec 14-Dec 23-Aug	Receive Receive High Stl High Stl Image: Start Finish Date Date 1 to 6 20-Sep 23-Sep 23-Aug 27-Sep 1 to 6 30-Sep 7-Oct 9-Aug 23-Aug 1 to 6 25-Oct 27-Oct 9-Aug 23-Aug 1 to 6 25-Oct 27-Oct 9-Aug 23-Aug 1 to 6 25-Oct 27-Oct 9-Sep 25-Oct 3 to 6 4-Nov 11-Nov 16-Aug 9-Sep 1 & 2 18-Nov 22-Nov 16-Aug 23-Aug 3 to 6 26-Nov 3-Dec 30-Aug 9-Sep 1 & 2 10-Dec 14-Dec 23-Aug 6-Sep	ke Receive on Site Receive on Site High Stl Date High Stl Date Variance Lines Start Finish Start Finish Start Finish Start 1 to 6 20-Sep 23-Sep 23-Aug 27-Sep 28 3 to 6 30-Sep 7-Oct 9-Aug 23-Aug 52 1 & 2 14-Oct 18-Oct 2-Aug 9-Aug 73 1 to 6 25-Oct 27-Oct 9-Sep 25-Oct 46 3 to 6 4-Nov 11-Nov 16-Aug 9-Sep 80 1 & 2 18-Nov 22-Nov 16-Aug 9-Sep 88 1 & 2 10-Dec 14-Dec 23-Aug 6-Sep 109

HNB - Shop F	abrication of St	eel Girder Spar	IS
27-Jul-21			
*excl. Line A	ssembly/Paintir	ng/Shipping	
Girder	Series Fab	Job Fab	
Series	% Complete	% Complete	
А	98%	5%	
В	100%	11%	
С	100%	6%	
D	44%	7%	
E	90%	6%	
F	43%	4%	
G	6%	0%	
Н	17%	3%	
I	75%	5%	
J	0%	0%	
К	77%	4%	
		51%	
		Line %	Job%
Parallel Girde	er Complete	61%	41%
Haunched Gi	rder Complete	31%	10%



Follow on Challenges

Equipment parts availability •

McLean

- Winter weather •
- High winds •
- •









SKANSKA SCO



Photo credit High Steel

Girder Logistics

McLean

- Haunched girders shipped horizontally and up-righted at the jobsite using a custom fabricated hitch
- Constant depth girders shipped vertically
- Majority of girders staged at the jobsite along the site access road
- Girder pairs assembled on transport barge
- Each barge load had an engineered loading and unloading plan





Haunched Girder Erection







McLean

SKANSKA SCORMAN



888 Ringer Used to Erect Steel Girders





Custom Fabricated Spreader Beams/Frames

Rigging consisted of standard slings/shackles/girder clamps





SKANSKA SCI

Access

McLean

- Crew boats transported craft to barges/piers
- Stair tower installed at channel piers
- Fall protection installed on each girder during pre-assembly on barges
- Job specific bolt up frames fabricated
- Crane mats placed on girders to stage equipment and materials



SKANSKA SCOR

- Erection sequence required postponing erection of flanking precast girder spans and drainage roughs
- Drop in span required jacking haunched girders to close a gap allowed for girder entry
- Bolt tensioning employed "turn of the nut"
- Stay in place decking used installation performed after field survey and camber checks
- Studs field installed

McLean

 Touch up painting performed in two stages – areas concealed or having restricted access and upper regions of girders performed prior to decking – balance of touch up performed using underbridge access equipment after the deck and barrier were placed





Nice Middleton Bridge Open 10/12/22



For more information, please visit us at: https://mdta.Maryland.gov/NiceMiddletonBridge/Home





NOW OPEN! On Budget, Months Ahead of Schedule

We finished ahead of schedule and had a blast!

Thank You

